

TENDER SCHEDULE FOR THE RENOVATION OF CANTEEN OF KERALA BANK , KURUPPAM ROAD, THRISSUR.

APPX A - (CIVIL WORKS)						
Sl.no	Particulars	Qty.	UNIT	RATE		Amount
				Figures	Words	
1	OD Demolishing brick/ Latrate masonry work and granite finished washing trough manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	1	M3			
2	13.1.1 12 mm cement plaster on the rough side of single or half brick wall of mix : C.M 1:4	15	M2			
3	13.43.1 Applying one coat of waster thinnable cement primer of approved brand and manufacturd on wall surface : Water thinnable cement primer	15	M2			
4	13.60.1 Finishing walls with Premium Acrylic emulsion paint with silicone additives of required shade :New work (Two or more coats applied @ 3.84 kg/10 sqm).	15	M2			
5	4.67.1 Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade : Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface.	200	M2			
6	OD Supplying and fixing stainless steel Kitchen Sink (size 560x400x25 mm or nearest size) with accessories of approved quality: Kitchen sink single bowl with drain board, approved by engineer. Make: Nirali/Futura/Equivalent	3	Nos			
7	OD Supplying and fixing Sink cock with wall flange of approved quality. Make: Jaquar/ Cera/ Hindware/ Equivalent	3	Nos			
8	OD Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 100 cm spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-charge.Consealed work,including cutting chased and making good the wall etc.	10	M			

9	OD Supply, installation, testing & commissioning of Wash basin (Simple counter & Oval shaped), white colour of approved quality. Make: Jaquar/ Cera/ Hindware/ Equivalent	3	Nos				
10	OD Providing & Laying vitrified wall tiles of size 1200x 600 mm in defferent size, with water absorbtion less than 0.08% and con firming to IS: 15622 of approved make, in all colour and shades, paisted by using approved cementing material and pointed with epoxy the joints with matching colour etc. complete.	120	M2				
11	Painting: with synthetic enamel paint for existing doors and windows including all cost etc complete	27	M2				
12	Acid-based cleaning for ceramic tiled floors and walls. Heavy Duty Tile Cleaner is designed for removal of cement film residues,efflorescence and most oxid stains.It may also be used as general purpose cleaner on other acid resistant surface.	75	M2				
	TOTAL					Rs.	
	GST 18 %					Rs.	
	GRAND TOTAL					Rs.	
	(Words)						
CONTRACTOR GENERAL MANAGER							

TENDER SCHEDULE FOR THE RENOVATION OF CANTEEN OF KERALA BANK , KURUPPAM ROAD, THRISSUR.

APPX B - (INTERIOR WORKS)						
Sl.no	Particulars	Qty.	UNIT	RATE		Amount
				Figures	Words	
1	Solid Flush Doors Supplying and fixing single leaf 32mm thick solid core flush door shutters.shutters finished with 1 mm laminate on both sideds. providing 8mm thick plain glass vision panel size 20 x 45cm. Rates including providing necessary fittings such as door closers, bearing hinges, door	1.68	M2			
2	Storage The width of the cupboard is 45 cm as shown in the drawing .all other horizontal and vertical partitions are made of 19 mm thick marine plywood IS 303. the front partition of the cupboard is to be provided with sliding shutters 19 mm thick , all visible areas finished with 1mm thick laminated finished	18	M2			
3	Providing & Fixing Cooking Counter Table/Wash counter table /Sink counter Table a) Steel work in built up tubular GP (Round,squareor rectangular hollow tubes etc.) for frame work of cooking table, including cutting, hoisting & fixing in position and applying a priming coat of approved steel primer, including welding etc. complete.	135	Kg			
	b) Provide 18 mm thick multi wood covered(both top & sides) over the existing GP tube frame. All sides (both inside & out side) painted with sinthetic enamel paint with approved colour, except top. Top finish with 18 mm thick granite slab with necessary grooves/ holes and including all necessary hardwares and fittings (Make: Hitachi/Hafele/ equivalent). provide hinged door at front side with locking arrangement etc. complete.					

	1) Cooking counter table - Width - 60 cm	4.00	M2				
	2) Cooking counter table - Width - 60 cm	2.20	M2				
	3) Cooking counter table - Width - 120 cm	2.00	M2				
	4) Wash counter table - Width - 60 cm	1.75	M2				
	5) Sink counter table - Width - 60 cm	3.20	M2				
4	Supply and fixing Bank Logo & advertisement as per the specified format & colour shade etc. complete	1	No				
	TOTAL					Rs.	
	GST 18 %					Rs.	
	GRAND TOTAL					Rs.	
	(Words)						
CONTRACTOR GENERAL MANAGER							

—
—
=

